BRUHAT BANGALORE MAHANAGARA PALIKE

SCHEDULE-B

Name of Work: Improvements to Roads and drains at R.K.Hegdenagara and surrounding areas in ward no:6 Thanisandra, Byatarayanapura Subdivision

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	394.88	KSRRB 300-1. **Earthwork excavation** by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 **(Page No141., I.No.19.1 of KPWD S.R 2015-16).**	Cum	83.16	Rupees Eighty Three And Paise Sixteen Only
2	633.60	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. 10cm thick(Page No 25., I.No.5.31.2 of KPWD S.R 2015-16).		794.88	Rupees Seven Hundred Ninety Four And Paise Eighty Eight Only
3	23.85	KSRB 4-1.2 : Providing and laying in **position plain cement concrete of mix1:3:6** with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregtes @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted,in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No. KBS 4.1, 4.2**(Page No 12., I.No.4.2 of KPWD S.R 2015-16)**	Cum	5236.92	Rupees Five Thousand Two Hundred Thirty Six And Paise Ninety Two Only
4	83.48	Providing and laying **Plain /reinforced cement concrete** for Box drain walls of thickness 10cm to 20cm including centring shuttering for work etc. complete as per approved drawing and design MORTH specification No.1500,1700,2200 **(Page No258., I.No.37.59.2 of KPWD S.R 2014-15).**	Cum	6954.12	Rupees Six Thousand Nine Hundred Fifty Four And Paise Twelve Only
5	7.17	KSRB 4.9.2 : Providing **T .M.T steel reinforcement** for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 for TMT Bars Fe500 **(Page No 17., I.No.4.46.2 of KPWD S.R 2014-15).**	Tonne	59327.91	Rupees Fifty Nine Thousand Three Hundred Twenty Seven And Paise Ninety One Only
6	531.00	Providing precast slab of 100 mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc.,complete as per the direction of engineer in charge- Data rate	Sqm	1834.00	Rupees One Thousand Eight Hundred Thirty Four Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

7	39.00	Providing precast slab of **250mm thick** including cost of all materials, labour, curing,transportation,loading ,unloading,etc.,complete as per the direction of engineer in charge- Data rate	Cum	5111.00	Rupees Five Thousand One Hundred Eleven Only
8	170.63	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2015-16	Cum	5070.60	Rupees Five Thousand Seventy And Paise Sixty Only
9	113.75	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 for raft foundation, column footing, main and secondary beams. Page No. 18/ Item No. 4.48/ PWD SR 2015-16	Cum	6332.04	Rupees Six Thousand Three Hundred Thirty Two And Paise Four Only
10	1137.50	Vaccum De- writing with vaccum pump and suction mat and compaction with skin flater clubbed with floatiog disc including cost of generator, HOM of machinery Sereed Vibratory Power Floaterblade and diisc etc. with all lead and lift No. 171/ Item No. 22.7/ PWD SR 2015-16	Sqm	97.20	Rupees Ninety Seven And Paise Twenty Only
11	168.00	Providing groove cutting for width of 5mm to 100m depth 80mm-100 including cost of cutting machine, generatoe & HOM of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot birumen fillars, and filler metal etc., including cost of conveyance of all materials,. Labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. No. 187/ Item No. 22.7/ PWD SR 2015-16	mtrs	124.20	Rupees One Hundred Twenty Four And Paise Twenty Only
12	394.88	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123,	Cum	73.36	Rupees Seventy Three And Paise Thirty Six Only

EXECUTIVE ENGINEER-4
KHRDL, BBMP DIVISION
BENGALURU-560 010

Signture of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92